CONCRETE CYLINDER COMPRESSION TEST REPORT



Neocrete Ltd

7 Doctors Common

Mt. Victoria

Wellington 6011

Attention: Zarina Bazoeva/Matt Kennedy-Good

Project: **D5 testing**

Cement sample : Golden Bay Cement 'Eversure' Type GP (25 kg bags)

D5 sample: n/a

Concrete mixed by: WSP Opus Research

Date mixed: **02/04/2019**

Batch volume: 35 L Grade: 35 MPa

Actual slump (mm): 150 (Note 2)

Specified slump (mm): 140+/-10

Project No: 524F25.00
Lab Ref No: 4-19/453
Client Ref No: D5 - Control

Test Results							
		2/04/10		5.10	4/10		
Date tested		3/04/19			4/19		
Age at test	(days)	24 hrs		:	3		
Average diameter	(mm)	100.4	100.1	100.1	100.2		
Height	(mm)	200.0	200.0	199.5	199.5		
Height to diameter ratio		1.99	2.00	1.99	1.99		
Compressive strength	(MPa)	8.5	9.0	22.5	22.0		
Corrected comp.strength (Note 1)	(MPa)	-	-	_	_		
Ave compressive strength	(MPa)	9.0		22	2.5		
Ends capped		None	None	None	None		
Defects prior to testing		None	None	None	None		
Failure mode		Normal	Normal	Normal	Normal		

Test Methods	Notes			
Compressive strength: NZS 3112:Part 2: 1986 Clauses 5 & 6	1. Strengths of specimens with height to diameter ratio			
Capping: NZS 3112: 1986, Pt 2 Clause 4 (amendment No 2 2000)	1.00 to 1.90 are corrected to account for the effect of the			
	reduced height to diameter.			
Correction for height to diameter ratio: in-house method CL-04-511.	2. Fresh concrete properties have been reported separately.			
	3. 7 & 28 day strengths will be reported separately as p2.			

Date reported: 08/04/19

IANZ Approved Signatory

D. Wong

Designation: Concrete Technologist

Date: 08/04/19

Testing is covered by IANZ Accreditation This report may only be reproduced in full



All tests reported herein have been performed in accordance with the laboratory's scope of accreditation

CSF 2093 (13/9/2006, modified 07/01/2008)

Page 1 of 2